

# Work Zone ITS Implementation Tool Users Guide

VERSION 2.0

PREPARED FOR: FEDERAL HIGHWAY ADMINISTRATION  
J. LAKE TRASK, MICHAEL ANDERSON, ALAN PATE, BEHZAD  
AGHDASHI AND BASTIAN J. SCHROEDER

**Notice**

This document is disseminated under the sponsorship of the Department of Transportation in the interest of information exchange. The United States Government assumes no liability for its contents or use thereof. This report does not constitute a standard, specification, or regulation. The United States Government does not endorse products or manufacturers. Trade and manufacturers' names appear in this report only because they are considered essential to the object of the document.

**Quality Assurance Statement**

The Federal Highway Administration (FHWA) provides high-quality information to serve Government, industry, and the public in a manner that promotes public understanding. Standards and policies are used to ensure and maximize the quality, objectivity, utility, and integrity of its information. FHWA periodically reviews quality issues and adjusts its programs and processes to ensure continuous quality improvement

*Cover photo and chapter exhibits courtesy of Kittelson and Associates, Inc.*

---

<b>1. Report No.</b> FHWA-HOP-XX-YYY	<b>2. Government Accession No.</b>	<b>3. Recipient's Catalog No.</b>	
<b>4. Title and Subtitle</b> Work Zone Intelligent Transportation System (WZITS) Implementation Tool 2.0		<b>5. Report Date</b> September 2020	
		<b>6. Performing Organization Code</b>	
<b>7. Author(s)</b> Bastian Schroeder, Brandon Nevers, Lake Trask, Zach Bugg, Ellen Moshier (Kittelson and Associates, Inc.), Michelle Boucher (KCUS), Behzad Aghdashi (ITRE)		<b>8. Performing Organization Report No.</b>	
<b>9. Performing Organization Name and Address</b> Kittelson and Associates, Inc. 272 N Front Street, Suite 410 Wilmington, NC 28401		<b>10. Work Unit No. (TRAIS)</b>	
		<b>11. Contract or Grant No.</b> DTFH61-12-D-00049 - 5003	
<b>12. Sponsoring Agency Name and Address</b> Federal Highway Administration (FHWA) Office of Transportation Operations 1200 New Jersey Ave., SE Washington, D.C. 20590 <a href="http://www.fhwa.dot.gov/workzones">www.fhwa.dot.gov/workzones</a>		<b>13. Type of Report and Period Covered</b>	
		<b>14. Sponsoring Agency Code</b>	
<b>15. Supplementary Notes</b> FHWA Project Leader – Todd Peterson, FHWA Valuable assistance in the development of the guide was provided by the FHWA Work Zone Team and State Departments of Transportation in Massachusetts and North Carolina. We also acknowledge review of the WZITS tool and beta-testing feedback from other state agencies and volunteer reviewers.			
<b>16. Abstract</b> This practitioner-friendly user guide describes the Work Zone Intelligent Transportation Systems (WZITS) Implementation Tool, prepared for the Federal Highway Administration (FHWA), and provides step-by-step instructions for its use. The WZITS Implementation Tool implements the logic and methodology described in the 2014 <i>Work Zone Intelligent Transportation Systems Implementation Guide</i> ; users should refer to the implementation guide for information about the tool's underlying methods. The tool creates and manages a project file that provides users with (1) guidance during the WZITS decision-making process, and (2) a place to document the decisions made, along with relevant supporting information. The user guide includes four case studies that illustrate the use of the tool.			
<b>17. Key Words</b> Work zone, intelligent transportation systems, ITS,	<b>18. Distribution Statement</b> No restrictions. This document is available to the public.		
<b>19. Security Classification (of this report)</b> Unclassified	<b>20. Security Classification (of this page)</b> Unclassified	<b>21. No of Pages</b> 68	<b>22. Price</b>

## 1 TABLE OF CONTENTS

1	Introduction .....	1
1.1	Overview .....	1
1.2	Installation and Running.....	21.3
	Document Organization .....	2
2	WZITS Implementation Tool User Guide .....	5
2.1	Navigating the Tool .....	5
2.2	Starting a New Work zone ITS Assessment .....	7
2.3	Saving and Opening Projects .....	8
2.4	Work Zone ITS Tool Inputs.....	8
2.5	WZITS implementation tool Outputs.....	17
3	Case Studies .....	19
3.1	Case Study 1 - Road Widening in Raleigh, NC.....	19
3.2	Case Study 2 – Bridge Replacement in Andover, MA .....	24
3.3	Case Study 3 – North Washington Bridge in Boston, MA.....	28
3.4	Case Study 4 – Roadway Widening in Ashe County, NC .....	31
4	References .....	33
5	Appendix - Detailed Case Study Tool Reports.....	33

## 1 INTRODUCTION

This practitioner-friendly user guide describes the Work Zone Intelligent Transportation Systems (WZITS) Implementation Tool, prepared for the Federal Highway Administration (FHWA), and provides step-by-step instructions for its use.

The WZITS Implementation Tool implements the logic and methodology described in the [FHWA Work Zone Intelligent Transportation Systems Implementation Guide \(1\)](#); users should refer to the guide for information about the underlying methods incorporated into the tool. The tool creates and manages a project file that provides users with (a) guidance during the WZITS decision-making process, and (b) a place to document the decisions made, along with relevant supporting information. The user guide includes four case studies that illustrate the use of the tool.

### 1.1 OVERVIEW

ITS is the use of a broad range of communications-based information and electronics technologies to enhance transportation (1). Work zone ITS is the use of ITS to improve safety and mobility in and around work zones. Information provided by work zone ITS may be in the form of real-time traffic conditions, such as travel delays through a work zone, or recommended diversion routes. This information can be used by motorists to alter their travel behavior, and by contractors and transportation agencies to alter traffic control strategies, traveler information, or work schedules. A work zone ITS deployment can be focused solely around safety or mobility, but it often supports both goals and can also help enhance productivity.

The WZITS Implementation Tool provides three core types of inputs, guidance, and documentation:

1. *Project Information*
2. *Project Wizards*
3. *Project Documentation*

*Project Information* inputs provide project reference information for the work zone and allow the user to add customized project documentation in addition to the standard inputs. General information about the overall roadway facility and the work zone scenario can also be specified using these inputs.

*Project Wizards* aggregate user inputs according to the guidance of the *Work Zone ITS Implementation Guide*. The wizards also provide decision-support through recommendations relating to project goals, ITS feasibility, team members and stakeholders, and potential ITS applications. The user can then combine the tool's recommendations with their own knowledge about a specific roadway and work zone when making decisions.

Lastly, *Project Documentation* questions reflect the guidance of the *Work Zone ITS Implementation Guide*. These questions are intended to ensure that the user has considered particular steps or aspects of the implementation process. This section of the tool also provides a place to document the decisions made over the course of the project.


## 1.2 KEY CHANGES

- Enhanced user-friendliness and interface facelift – simplified tool navigation with a more modern look and feel.
- Streamlined installation process, now independent of Java – Users no longer need to have Java installed on their computer to use WZITS, simply download the Windows Installer file (.msi) and install.
- Ability to change wizard scoring by agency
- Streamlined presentation of Steps 3-6
- Fact sheet improvements
- Comment Fields for most data entries – Comments useful for justification or reasoning for a certain selection.
- Pop-up windows for most fields
- Bug fixes and minor updates – Notably the concept of operations image now correctly saves with the file.


## 1.3 INSTALLATION AND RUNNING

To install the Work Zone ITS Implementation tool, download the Windows installer file (.msi) from the following link: [https://github.com/kittelton/WZITS\\_Tool](https://github.com/kittelton/WZITS_Tool). Once the file has downloaded, double-click the file to launch a guided installation wizard (Figure 1). Follow the instructions of the installation wizard to install WZITS. If desired, a specific install location can be specified for the program, but in general the standard location in C:\Program Files\WZITS TOOL should suffice for most users (see Figure 2). Note that installing the program will require administrator privileges for the computer.

Once the installation wizard has finished, both a desktop shortcut and a start menu item will have been created and can be used to launch the program.




**Figure 1: Step one of the WZITS Tool guided installation wizard.**



**Figure 2: The WZITS Tool installation wizard with the default installation location for the tool.**

Optional:

There are two options to uninstall WZITS. First, if the original installer is available, launching the install wizard provides an option to Uninstall WZITS (Figure 3). Alternatively, WZITS can be uninstalled using the “Add or Remove Programs” Windows built-in utility.



**Figure 3. The WZITS tool installation wizard can be used to uninstall the WZITS Tool.**

## 1.4 USER GUIDE ORGANIZATION

Section 0 of this user guide focuses on how to use the software. First, Sections 2.1 through 2.3 outline the tool's basic structure and features, including how to navigate through the software, how to start a new work zone ITS assessment, and how to save and reopen projects. Next, Section 2.4 provides a detailed discussion of the tool's outputs. Finally, Section 2.5 describes the outputs produced by the tool.

Section 0 provides four case studies demonstrating how to use the tool; the appendix in Section 5 provides detailed output reports for each case study. Finally, Section 5 provides a reference to the *Work Zone ITS Implementation Guide*.




## 2 WZITS IMPLEMENTATION TOOL USER GUIDE

This section presents an overview of the WZITS Implementation Tool and provides step-by-step descriptions on how to interact with the tool's various components. Screenshots are used extensively to illustrate key points. The focus is on user interaction with the tool, as opposed to a discussion of the individual steps of a WZITS assessment and their respective inputs. Section 2.4 provides a brief overview of these steps and their underlying logic; more detailed information can be found in the *Work Zone ITS Implementation Guide (1)*.

### 2.1 NAVIGATING THE TOOL

The general layout of the tool's main window is shown in Figure 4. This window contains five key components, as indicated by the numbers in Figure 4:

1. Project Menubar
2. Project Workflow Toolbar
3. Step Navigator
4. Main Input Window
5. Project Dashboard



**Figure 4: General Layout of the WZITS Implementation Tool.**

The *Project Menubar* (#1 in Figure 4) provides access to various commands and options, similar to the menus provided in any other application. The usage of these menu commands will be described as needed throughout Section 2.

The *Project Workflow Toolbar* (#2 in Figure 4) is located just below the menubar. The toolbar serves as both the primary navigational control for the tool and as a visual reference to where the user is in the WZITS assessment process. Section 2.1.1 discusses the use of the toolbar.

The *Step Navigator* (#3 in Figure 4) is located on the left side of the window. The steps involved in a WZITS assessment are displayed in the navigator in an expandable/collapsible tree format. Double-clicking any item in the tree will navigate directly to the corresponding step or sub-step in the assessment process.


The *Main Input Window* (#4 in Figure 4) occupies the center of the window. This area provides the inputs and outputs relevant to a specific step or sub-step of a WZITS assessment and its content changes as different steps are selected in the Project Workflow Toolbar or Step Navigator. The screenshot in Figure 4 shows the introduction screen that is displayed in the main input window each time the tool is launched.

Finally, the *Project Dashboard* (#5 in Figure 4) is hidden until the bar at the bottom of the window is clicked, thereby expanding the dashboard into the bottom section of the window. The dashboard displays the progress made in the WZITS assessment and provides key assessment milestones. Section 2.1.2 describes the dashboard in more detail.

### 2.1.1 PROJECT WORKFLOW TOOLBAR

Figure 5 displays views of the Project Workflow Toolbar in its collapsed and expanded states. In the toolbar's collapsed state (Figure 5a), only the top-level steps in the process are shown. In the toolbar's expanded state (Figure 5b), a selected step (in this case, Step 1) is expanded to display all the substeps associated with that step.

One function of the toolbar is to visually indicate the progress made in the WZITS assessment. The step currently being worked on is highlighted. In Figure 5a, the tool has just been opened with a new project and the “Intro” step is highlighted. None of the steps in the process have been worked on yet; these are displayed in a light blue color. In Figure 5b, Step 1 has been opened to reveal all the sub-steps associated with Step 1. The user has already worked on all the sub-steps in Step 1, as the light blue color has been replaced with brighter colors in each sub-step. Sub-steps shown with a brown background are ones where the user provides input to the tool or views tool output via the Main Input Window; these sub-steps turn orange when selected (for example, the Team Members sub-step is currently being worked on in Figure 5b). Sub-steps shown with a dark green background have an associated wizard for providing input, as described in Section 2.4.2; these sub-steps turn light green when selected.



**Figure 5: Close-up View of the Project Workflow Toolbar.**

The toolbar's second function is to serve as the tool's main navigational control. The arrow buttons on the right and left sides of the toolbar allow the user to step forward and backward through the WZITS assessment. The individual step icons expand and collapse as the user

navigates through them and the sub-step currently being worked on is highlighted. In addition, the name of the current step being worked on is displayed in the grey bar at the top of the toolbar. The step and sub-step icons also double as buttons that can be used to jump directly to a specific step or sub-step.


### 2.1.2 PROJECT DASHBOARD

The Project Dashboard provides real-time feedback about project progress made and key assessment conclusions. By default, the project dashboard is collapsed, but it can be expanded by clicking the bar at the bottom of the window. In its collapsed state (Figure 6), the dashboard provides progress bars denoting progress toward the four key assessment milestones: Goals Selection, Feasibility Assessment, Stakeholders, and Applications. The progress bars are displayed in orange while the assessment is in process. The bars change to green once the all the requirements to reach the milestone have been completed.



**Figure 6: Example of the Project Dashboard in its Collapsed State.**

In its expanded state (Figure 7), the Project Dashboard provides more detailed information about the progress of the WZITS assessment. Five tabs are provided: one for each of four assessment milestones, and a fifth with general project information. Indicators next to each tab show progress toward completing a milestone in orange with percent complete, changing to green and “Ready!” once the milestone is reached. In Figure 7, the user has selected the Goals tab. This tab shows the top goal that the user has selected out of each category of goals. The dashboard tabs can be a useful way to view important information from previous steps without having to navigate back to the step or sub-step in the Main Input Window.



**Figure 7: Example of the Project Dashboard in its Expanded State.**

## 2.2 STARTING A NEW WORK ZONE ITS ASSESSMENT

After starting the program, the user can create a new project or open an existing project. Opening an existing project is described next in Section 2.3. To begin a new WZITS assessment, press the large blue button at the bottom of the introduction screen, or navigate to Step 1 using the forward arrow in the Project Workflow Toolbar.

The first screen of each step provides a title card displaying the name of the corresponding step in the *Work Zone ITS Implementation Guide*, along with the names of the sub-steps associated with that step. While the tool's six main steps are consistent with the six steps presented in the *Work Zone ITS Implementation Guide*, the tool makes some changes to selected sub-steps to better facilitate the use of the guidance for design and decision-making purposes. For example, the feasibility assessment has been moved earlier in the process to provide a more timely assessment of when to proceed to use the tool.

Figure 8 shows an example of the title card for Step 1. The sub-steps shown in orange correspond directly to sections in the *Work Zone ITS Implementation Guide*; the specific section number is shown for reference in a dark gray box below each of the orange sub-steps. For example, guidance for the User Needs sub-step can be found in Section 1.1 of the implementation guide. Sub-steps shown in light grey indicate inputs unique to the tool (general project information in this case). Finally, sub-steps shown in green are decision-support “wizards” that aggregate information from previous sub-steps to provide actionable items and interim outputs. These “wizards” are not explicitly described in the implementation guide; rather, they provide helpful structure to the guide’s decision-making process.



**Figure 8: Title Card for Step 1: Assessment of Needs.**

## 2.3 SAVING AND OPENING PROJECTS

The tool saves projects files in a custom .wzp format. To save a file, select either “Save Project” or “Save Project As” from the File menu. “Save Project As” can be used to save the file in a new location, with a new name, or both. If the active project has been saved previously, “Save Project” will write any new changes to the existing file. If the project has not yet been saved, “Save Project” will function the same as the “Save Project As” option.

To open a project file, select “Open Project” from the File menu and use the file explorer to select the desired .wzp file.

## 2.4 WORK ZONE ITS TOOL INPUTS

The tool’s inputs can be divided into three categories: project information, wizard inputs, and project documentation. The majority of the tool’s inputs fall into one of the two latter categories. The following subsections describe how to interact with each of the three input types.

## 2.4.1 PROJECT INFORMATION AND FACILITY CONFIGURATION

The tool's initial step, Introduction, is a new step that is not explicitly described in the *Work Zone ITS Implementation Guide*. This step allows the user to input general project reference information and to describe the overall roadway facility and work zone configuration. Inputs for this step are entered through a combination of text fields, drop-down choice boxes, and direct numerical inputs, as shown in Figure 9. General project information inputs are entered in the left-hand column within the Main Input Window, while facility and work zone configuration inputs are entered in the right-hand column.

**Figure 9: Project Information and Facility Configuration Inputs.**

The user can optionally specify the following information about each project:


- State Agency
- Analyst
- Project Name
- Project Description
- Project Limits
- Project Website Link
- Project Photo

These inputs are used solely for record-keeping and documentation purposes, and it is to the user's discretion as to how much (or how little) information to provide.

Next, the user should provide a set of inputs relating to the facility and work zone configuration. These inputs are not meant to provide an exhaustive description of the facility and work zone. Rather, they are a subset of commonly used information that the tool uses to facilitate project documentation and the tool's decision-making logic. Many of the inputs are used to preemptively provide answers to questions where possible in later steps of the assessment.

Where available, more information about a particular input can be viewed by clicking on an orange “?” next to the input name (see Work Zone Type in Figure 9).

As these inputs may not provide a complete picture of particular aspects of the facility or work zone, the user can optionally provide additional notes for an input by clicking the “Add Comment” link directly to the right of that input. Doing so will launch a small popup window with space for entering additional comments. These comments will be displayed later on in the documentation for the step. Figure 10 shows an example of the popup window for roadway functional class.



**Figure 10: Example of an “Additional Comments” Popup Window.**

---

## 2.4.2 WIZARD-STYLE INPUTS

Four decision-support “wizards” have been incorporated into the tool to provide guidance and decision-making support. The four wizards facilitate:

1. Selecting project **goals** for the use of work zone ITS,
2. Assessing the **feasibility** of using work zone ITS strategies for the project,
3. Selecting the **stakeholders** and team members most likely to be affected, and
4. Identifying the WZITS **applications** or technologies most likely to be effective for the project.

The Goals, Feasibility, and Stakeholder wizards are completed during Step 1 (as shown previously in Figure 8), while the Applications wizard is completed as the first activity in Step 2.

Using the wizard largely consists of answering a series of yes-or-no questions, although some wizards require additional inputs in the form of drop-down choice boxes. Figure 11 shows an example of the questions asked by the Goals wizard. The user should answer these questions to the best of their ability. In the event that a question is not applicable to a particular project, answering “No” will generally remove the question from consideration in scoring. Questions that are “greyed out” have been answered previously or are considered to be not applicable based on previous inputs.

User Needs			User Response	
#	Input Question	Yes	No or N/A	
1	Do you expect congestion impacts to be noticeable to roadway users?	<input type="checkbox"/>	<input type="checkbox"/>	
2	Is driver diversion expected onto alternate routes?	<input type="checkbox"/>	<input type="checkbox"/>	
3	Do you anticipate significant queuing as a result of this work zone?	<input type="checkbox"/>	<input type="checkbox"/>	
4	Will this work zone have reduced lane widths?	<input type="checkbox"/>	<input type="checkbox"/>	

Figure 11: Example of Inputs Required for the Goals Wizard.

Each question is linked to a scoring matrix that is used to quantify an aspect of the assessment and to provide the user with a recommendation. These scoring matrices have been pre-determined, drawing from the *Work Zone ITS Implementation Guide*, in combination with the beta testing and outreach performed for the implementation tool. If desired, users can customize the scoring matrices by directly editing the tool's source code.

After all of a wizard's questions have been answered, the wizard will use the scoring matrices to quantify its assessment. In the case of the Feasibility wizard, this process results in an immediate score and recommendation, as shown in Figure 12.

#	Input Question	User Response	Contributed Score	
1	What is the duration of long-term stationary work?	4-10 months	5	
2	To what extent will users be impacted for the duration of the work zone?	Moderate	5	
3	During which time periods are noticeable traffic impacts expected to occur?	During most of a single peak hour in a single dire...	1	
4	How long are queues expected to extend?	1-2 miles for 1-2 hours per day	5	
#	Mark All That Apply	User Response	Contributed Score	
		Yes	No or N/A	
1	Is traffic speed variability expected to occur?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	1
2	Do you expect back of queue and other sight distance issues?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
3	Are high speeds/chronic speeding expected to occur?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	2
4	Is driver diversion expected onto alternate routes? (See User Needs #2)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	1
5	Are merging conflicts and hazards at work zone tapers expected to occur?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
6	Do you expect the work zone layout to cause driver confusion or trouble wayfinding?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
7	Will frequently changing operating conditions for traffic be used?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
8	Will variable work activities occur?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
9	Are oversize vehicles expected?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
10	Do you expect a construction vehicle entry/exit speed differential relative to traffic?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	2
11	Will data be collected for work zone performance measures?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
12	Do you expect any unusual or unpredictable weather patterns to occur?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	3
Feasibility Score:		46	30 or more: ITS is likely to provide significant benefits and should be considered as a treatment to mitigate impacts.	

Figure 12: Example of the Outputs from a Feasibility Wizard Assessment.

In the case of the other three wizards, the tool provides a set of scored recommendations from which the user must make selections.

For example, the Goals wizard provides a set of recommended project goals, and the user is then asked to select the most important goals, drawing from the user's knowledge of the particulars of the project. An example is shown in Figure 13. Use the checkboxes in the right-most column to mark a specific goal for inclusion in the project. When provided, use an "edit" link to specify an aspect of a goal (e.g., to specify a maximum delay in the "Reduce daily peak period delays to XX minutes" goal).

Note that while the priorities listed for the goals are based on the *Work Zone ITS Implementation Guide*, **these priorities are not intended to be the sole factors in the decision-making process**; rather, they should supplement the user's knowledge and be used to provide an initial assessment.

**Work Zone ITS Tool** Step 1: Assessment of Needs & Feasibility

Use the checkboxes in the far right column to select goals for the project. These goals and their associated scores are based on user input from prior steps. Specific goals should be selected for emphasis for this project based on both the score recommendations and the analyst's judgement.


Category	Subcategory	Ranking	Selected
Safety	Reduce rear-end crashes	3	<input checked="" type="checkbox"/>
Safety	Reduce secondary incidents	3	<input checked="" type="checkbox"/>
Safety	Reduce Incident Clearance Times	3	<input checked="" type="checkbox"/>
Safety	Work toward zero work zone fatalities	3	<input checked="" type="checkbox"/>
Safety	Provide a safe environment for roadway users and worker safety	3	<input checked="" type="checkbox"/>
Mobility	Reduce variability of travel times	3	<input checked="" type="checkbox"/>
Mobility	Reduce daily peak period delays to XX minutes <a href="#">(edit)</a>	3	<input checked="" type="checkbox"/>
Mobility	Facilitate the movement of emergency and construction vehicles through the work zone	3	<input type="checkbox"/>
Mobility	Reduce the number of single-vehicle trips through the work zone	2	<input checked="" type="checkbox"/>
Productivity	Minimize delays in construction vehicle access to the work zone	1	<input type="checkbox"/>
Productivity	Provide an egress from work zone for haul vehicles	1	<input type="checkbox"/>
Regulatory	Monitor work zone operations and safety performance in real-time	3	<input type="checkbox"/>
Regulatory	Monitor alternative route operations and safety performance in real-time	2	<input checked="" type="checkbox"/>
Regulatory	Optimize contractor work periods	2	<input checked="" type="checkbox"/>
Traveler Info	Provide roadway users real-time work zone information	2	<input checked="" type="checkbox"/>
Traveler Info	Provide roadway users real-time alternate route information	2	<input type="checkbox"/>

Project Milestones: Goals ☒ Feasibility Assessment ☒ Stakeholders ☐ Applications ☐

**Figure 13: Example of the Goals Selection Step of the *Goals Wizard*.**

Once the desired project goals have been selected from the list of recommended goals, the wizard's final step summarizes the selected goals, as shown in Figure 14. The selected goals will also appear in the fact sheet output for Step 1 (described in Section 2.5). In addition, the user can return to this sub-step at any time for reference.





**Figure 14: Example of Selected Goals Step of the Goals Wizard.**

The Stakeholder wizard follows a similar three-step process of answering input questions, selecting project stakeholder and team members from a set of recommendations, and displaying a summary of the user's selections. Figure 15 shows an example of the Stakeholder wizard's input questions window, while Figure 16 shows an example of the team member recommendations produced by the wizard, along with their relative priorities. The user can mark agencies and groups as *core team members*, *stakeholders*, or *parties with little to no interest* (represented by the "N/A" column). Agencies or groups for which no selection is made are automatically placed into the "little to no interest" category.

Figure 17 shows an example of the Stakeholder wizard's summary results screen. The "edit" links next to each team member, stakeholder, and other organizations can be used to specify contact information and other relevant information, such as organization names. When clicked, these links open a pop-up window similar to the example shown in Figure 18 for a city transportation agency. The information entered in these pop-up windows will be stored in the project file for reference and will be displayed in an abbreviated manner in the fact sheet outputs.

**Work Zone ITS Tool - New Project**

File Analysis Results Help

**Work Zone ITS Tool Step 1: Assessment of Needs & Feasibility**

Step 1 General Info User Needs Goals Selection Selected Goals Feasibility Assessment Stakeholder Assessment Stakeholders & Team Selection Team Members ITS Resources Step 1 Report 2 3 4 5 6

**Stakeholder Assessment**

#	Input Question	User Response
1	What agency is responsible for responding to incidents/patrolling the roadway?	Local Police/Sheriff
2	Will the work zone require lane closures? (Specified in WZ Metadata)	Yes
3	What is the functional classification of the associated roadway(s)? (Specified in WZ Metadata)	
4	Is the associated roadway(s) maintained by the state, county, or city/town? (Specified in WZ Metadata)	

#	Mark All That Apply	User Response	
		Yes	No or N/A
1	Are there schools or universities in the area?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2	Do you expect a high percentage of tourists or unfamiliar drivers using the routes?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
3	Is there a special event venue nearby?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4	Does a transit line run parallel to the work zone?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
5	Are there other work zones in the area?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
6	Is the work zone located on a priority route for an emergency response system? (more info)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
7	Are there local businesses/shopping centers located near the work zone?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
8	Will there be restrictions to side streets?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9	Is this a freight or shipping corridor?	<input checked="" type="checkbox"/>	<input type="checkbox"/>
10	Are there ped/bike routes impacted by the work zone?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
11	Is the work zone on a roadway that is part of a signalized / coordinated system?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
12	Is there a concern the work zone will cause unwanted diversion onto local roads?	<input type="checkbox"/>	<input type="checkbox"/>
13	Is there a mobility goal? (Refer to "Goals" Step)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
14	Is there a productivity goal? (Refer to "Goals" Step)	<input type="checkbox"/>	<input checked="" type="checkbox"/>
15	Is there a regulatory goal? (Refer to "Goals" Step)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
16	Is there a safety goal? (Refer to "Goals" Step)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
17	Is there a traveler information goal? (Refer to "Goals" Step)	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Project Milestones: Goals Feasibility Assessment Stakeholders Applications

Figure 15: Example of Stakeholder Wizard Inputs.

**Work Zone ITS Tool - New Project**

File Analysis Results Help

**Work Zone ITS Tool Step 1: Assessment of Needs & Feasibility**

Step 1 General Info User Needs Goals Selection Selected Goals Feasibility Assessment Stakeholder Assessment Stakeholders & Team Selection Team Members ITS Resources Step 1 Report 2 3 4 5 6

**Stakeholders & Team Selection**

#	Name	Priority	Team Members		
			Core Team	Stakeholder	N/A
1	Local police/Sheriff	High	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2	Fire department	Medium	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
3	EMS	Medium	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
4	Motorists	Medium	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5	Traffic Management Center	Medium	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
6	City transportation agency	Low	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
7	Transit agency	Low	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
8	Local businesses	Low	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
9	Commercial trucking companies	Low	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
10	Incident management agencies	Low	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
11	Media	Low	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
12	Local residents	Low	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
13	Special event venue	Low	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
14	Schools/ Universities	Low	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
15	State DOT	Low	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
16	County transportation agency	Not Recommended	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
17	MPO	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
18	FHWA Division Office	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
19	Service patrol/Contractors	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
20	Construction contractors	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
21	State police	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
22	Shopping centers	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
23	Public officials	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
24	Convention/ Visitors Bureau	Not Recommended	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Project Milestones: Goals Feasibility Assessment Stakeholders Applications

Figure 16: Example of Stakeholder Wizard Team Member Selection.

**Work Zone ITS Tool - Step 1: Assessment of Needs & Feasibility**

**Team Members**

#	Name	Email	Phone #
<b>Selected Core Team Members (Add Additional)</b>			
1	State DOT (edit)		
2	Local police/Sheriff (edit)		
3	Motorists (edit)		
4	Media (edit)		
5	Local residents (edit)		
6	Incident management agencies (edit)		
7	Traffic Management Center (edit)		
<b>Selected Project Stakeholders (Add Additional)</b>			
1	Transit agency (edit)		
2	Fire department (edit)		
3	EMS (edit)		
4	Local businesses (edit)		
5	Commercial trucking companies (edit)		
<b>Agencies with Unlikely Interest (Add Additional)</b>			
1	County transportation agency (edit)		
2	City transportation agency (edit)		
3	MPO (edit)		

Project Milestones: Goals █████ Feasibility Assessment █████ Stakeholders █████ Applications █████

Figure 17: Example of the Stakeholder Wizard Summary Step.

**Enter/Edit Stakeholder Contact Information**

Contact Name: \_\_\_\_\_

Phone #: \_\_\_\_\_

Email: \_\_\_\_\_

Comment: \_\_\_\_\_

**Save** **Cancel**

Figure 18: Example of the Stakeholder Contact Information Pop-up Window.

## 2.4.3 EDITABLE WIZARD SCORING BY AGENCY

This worksheet contains the underlying WZITS Feasibility Matrix. The Yellow backgrounded cells can be edited by the user to reflect custom scores for a specific question.

Criteria	Question	Answer	Score	Response	Points		
<b>1 Duration of work zone</b>							
	What is the duration of long-term stationary work?	> 1 construction season	8	No	0		
		4-10 months	5	No			
		< 4 months	1	No			
<b>2 Impact to traffic, businesses, other destinations, or other users (e.g., extremely long delays, high risk of speed variability, access issues)</b>							
	To what extent will users be impacted for the duration of the work zone?	Significant	8	No	0		
		Moderate	5	No			
		Minimal	1	No			
<b>3 Queuing and delays</b>							
	How long are queues expected to extend?	At least 2 miles for at least 2 hours per day	8	No	0		
		1-2 miles for 1-2 hours per day	5	No			
		Less than one mile for less than one hour per day	1	No			
<b>4 Temporal Aspects of Traffic Impacts</b>							
	During which time periods are noticeable traffic impacts expected to occur?	More than morning and afternoon peak hours in both directions	6	No	0		
		During most of the morning and afternoon peak hours in either	3	No			
		During most of a single peak hour in a single direction	1	No			
	Unpredictable		0	No	0		
<b>5 Specific Issues</b>							
	How many of the following issues are expected to occur? (Select all that apply)	Is traffic speed variability expected to occur?	1	No	0		
		Do you expect back of queue and other sight distance issues?	3	No			
		Are high speeds/chronic speeding expected to occur?	2	No			
		Is driver diversion expected onto alternate routes?	1	No			
		Are merging conflicts and hazards at work zone tapers expected to occur?	3	No			
		Do you expect the work zone layout to cause driver confusion or trouble w/ a finding?	3	No			
		Will frequently changing operating conditions for traffic be used?	3	No			
		Will variable work activities occur?	3	No			
		Are oversize vehicles expected?	3	No			
		Do you expect a construction vehicle entry/exit speed differential relative to traffic?	2	No			
		Will data be collected for work zone performance measures?	3	No			
		occur?	3	No			
<b>Score</b>							
<b>30 or more</b> ITS is likely to provide significant benefits and should be considered as a treatment to mitigate impacts					0		
<b>10 to 29</b> ITS may provide some benefits and should be considered as a treatment to mitigate impacts							
<b>less than 10</b> ITS may not provide enough benefit to justify the associated costs							

Feasibility: ITS may not provide enough benefit to justify the associated costs

**Export Feasibility Matrix**

Use the **Export** button to generate a custom scoring matrix for the standalone WZITS Tool. If there is a valid installation of the WZITS Tool (Version 2 or higher) on the computer, the matrix will be automatically created as a resource file for the tool. Any changes will be reflected once the WZITS tool is next opened.

Figure 17: Example of the editable Feasibility Matrix

## 2.4.4 PROJECT DOCUMENTATION INPUTS

The final type of input used by the tool are project documentation inputs. These inputs are not scored or used directly in the tool's decision-making guidance; instead, they provide records of the assessment steps that were taken along with all information relevant to the decisions that were made. This information is stored in the project file for future reference, and appears in the fact sheet outputs.

Project documentation inputs are presented in the form of questions and comment areas. The questions include yes-or-no questions, multiple-choice questions, and open-ended questions requiring the user to fill out a comment field with the relevant information and/or justification. Each question should be answered to the best of one's ability. The comments boxes can be used to indicate questions that are not applicable to a particular project. Figure shows an example of the project documentation inputs related to costs.

The screenshot displays the 'Work Zone ITS Tool' interface, specifically 'Step 2: Concept Development'. The top navigation bar shows a sequence of steps: 1 (Initial Applications), 2 (Application Wizard), 3 (Benefits), 4 (Costs), 5 (Institutional & Jurisdictional), 6 (Legal/Policy), 7 (Stakeholder Buy-In), 8 (Develop Concept of Operations), and 9 (Step 2 Report). The 'Costs' step is currently active. The sidebar on the left lists project milestones: Goals, Feasibility Assessment, Stakeholders, and Applications. The main content area is titled 'Costs' and contains five questions for input:

- 1: Will any sensors be deployed? (Yes/No)
- 2: Will portable variable message signs will be deployed? (Yes/No)
- 3: Will cameras will be deployed? (Yes/No)
- 4: Which ITS devices will be rented/leased? (Describe...)
- 5: Which ITS devices will be purchased? (Describe...)

Each question has a text input field for 'How many / what type? Additional comments...' and a 'Yes'/'No' checkbox. The bottom of the interface shows a progress bar for the project milestones.

**Figure 8: Example of Project Documentation Inputs.**

## 2.5 WZITS IMPLEMENTATION TOOL OUTPUTS

The tool generates eight fact sheet outputs over the course of the work zone ITS assessment. Steps 1 and 2 generate two fact sheets each, while Steps 3–6 generate one fact sheet each. These fact sheets aggregate the information input into the tool and the guidance determined from these inputs into a set of concise reference sheets.

The fact sheets can be accessed from the “Step Report” sub-step once all of the other sub-steps associated with that step have been completed. Figure shows an example of the first fact sheet generated in Step 1. Fact sheets can also be exported as PDF files by selecting “Export to PDF” from the Results menu, as shown in Figure .

**Work Zone ITS Tool** Step 1: Assessment of Needs & Feasibility

Report: Assessment of Needs & Feasibility

**Fact Sheet #1: Project Info and WZ Metadata**

<b>State Agency:</b>	FHWA		
<b>Analyst:</b>	John Doe		
<b>Date:</b>	08/18/2020		
<b>Project Name:</b>	WZITS Project		
<b>Project Description:</b>	This space is for a brief description of the WZITS project.		
<b>Project Limits:</b>			
<b>Signature Sign-Off:</b>	<a href="https://www.fhwa.dot.gov/">https://www.fhwa.dot.gov/</a>		
<b>Facility and Base Conditions</b>	Average Annual Daily Traffic:	50000	
	Functional Class of Roadway:	Principal Arterial	
	Maintaining Agency:	State	
	Area Type:	Urban	
	Number of Roadway Lanes (1 Direction):	3	
	Shoulder Width (ft):	10.0	
	Posted Speed Limit (mph):	55	
	Lane Width:	12.0	
	Signalized Corridor?	No	
	National Highway System?	No	
	Length of Work Zone (mi):	2.0	
<b>Work Zone Configuration</b>	Type of Work Zone (MUTCD):	Long-Term Stationary	
	Work Zone Speed Limit:	45	
	Number of Lanes to be Closed:	1	
	Work Zone Lane Width:	12.0	
	Shoulder Closure:	Yes	
	Federal-Aid Project:	Yes	
<b>Category</b>	Selected Work Zone ITS Goals		
	Reduce rear-end crashes		

Figure 9: Example of the First Fact Sheet of Step 1.

**Work Zone ITS Tool** Step 1: Assessment of Needs & Feasibility

Results

Export to PDF

Full Summary Report

Fact Sheet 1

Fact Sheet 2

Fact Sheet 3

Fact Sheet 4

Fact Sheet 5

Fact Sheet 6

Fact Sheet 7

Fact Sheet 8

**State Agency:** FHWA

**Analyst:** John Doe

**Date:** 08/18/2020

**Project Name:** WZITS Project

**Project Description:** This space is for a brief description of the WZITS project.

**Project Limits:**

**Signature Sign-Off:** <https://www.fhwa.dot.gov/>

Figure 20: Demonstration of Exporting a Fact Sheet in PDF Format.

### 3 CASE STUDIES

This section presents a set of four case studies that demonstrate example usages of the WZITS Implementation Tool. The focus of these case studies is largely on the early stages of the WZITS process, because some of the projects had not actually gone through ConOps, procurement, deployment, and WZITS system evaluation at the time of writing. Therefore, the case studies are intended to illustrate how an agency can use the *Work Zone ITS Implementation Guide* and implementation tool to assist in evaluating WZITS feasibility, goal setting, application, and stakeholder involvement. The case studies are introduced below and documented further in the appendix in Section 5.

#### 3.1 CASE STUDY 1: ROAD WIDENING IN RALEIGH, NC

The North Carolina Department of Transportation (NCDOT) completed a roadway widening project along Interstate I-40 in Raleigh, NC in 2011. This case study assumes that the implementation tool had been applied to the project prior to construction.

The project widened 6.2 miles of I-40 from west of Wade Avenue (State Road 1728) to east of the Jones Franklin Road (S.R. 5039) bridge. The project's stated goal was to reduce congestion and improve traffic flow in one of the most heavily congested areas in the Research Triangle. An overview map of the project is shown in Figure .




Figure 1: Raleigh, NC Case Study Overview (Source: NCDOT)

Lane closures were allowed between 9 p.m. and 6 a.m. Monday through Friday, until 9 a.m. on Saturday, and until 10 a.m. on Sunday. One extended weekend lane closure was allowed to occur from 9 p.m. Friday to 6 a.m. Monday in the eastbound lanes between Harrison Avenue and Wade Avenue.

The project was constructed using the design-build method. Design-build is an innovative procedure that allows NCDOT to conduct a project's design, environmental permitting, right-of-way acquisition, utility relocation, and construction concurrently under one contract. These steps help reduce construction time and help the department avoid cost inflation.

To minimize impact from construction vehicles, the contractor installed two conveyor belt systems near the N.C. 54 interchange to transport stone and asphalt to the median area. The contractor estimated that the use of the conveyors eliminated 237 lane closures and nearly 12,000 truck trips that otherwise would have been needed to haul the materials from the I-40 travel lanes. The conveyor belt system is shown in Figure .



**Figure 2: Photos of the Raleigh, NC Case Study Conveyor Belt System**

Following the guidance in *Work Zone ITS Implementation Guide* and the implementation tool's wizards, information about the I-40 widening project was used to complete Steps 1 and Step 2 of the work zone assessment process to determine the following:

- System goals;
- Feasibility of the project as a Smart Work Zone;
- Most applicable Smart Work Zone applications; and
- List of stakeholders.

Starting with the Goal Wizard, a series of twenty questions were answered related to the roadway geometry, expected congestion and queuing, and performance targets. Based on these responses, the wizard recommended a number of goals in the mobility, safety, productivity, regulatory, and traveler information categories and provided a ranking for each of these recommended goals (see Table 1). For the I-40 case study, the highest-ranked goals were:

- Mobility: reduce variability of travel times,
- Safety: reduce rear-end crashes, and



- Regulatory: Monitor work zone operations and safety in real-time.

Additional mobility goals included reducing delays and single-vehicle trips through the work zones. Additional safety goals included reducing secondary crashes and incident clearance times. These recommendations matched well with NCDOT's focus and policy for this work zone.

**Table 1: Goal Wizard Output for the Raleigh, NC Case Study**

Category	Recommended User Goals by WZITS Tool	Score
Mobility Goals	Reduce variability of travel times	High
	Reduce daily peak period delays to XX minutes	Medium
	Reduce the number of single-vehicle trips through the work zone	Medium
	Facilitate the movement of emergency and construction vehicles through the work zone	Medium
Safety Goals	Reduce rear-end crashes	High
	Reduce secondary incidents	Medium
	Reduce Incident Clearance Times	Medium
	Provide a safe environment for roadway users and worker safety	Medium
	Work toward zero work zone fatalities	Medium
Productivity Goals	Minimize delays in construction vehicle access to the work zone	Low
	Provide an egress from work zone for haul vehicles	Low
Regulatory Goals	Monitor work zone operations and safety performance in real-time	High
	Reduce work zone delays to within XX minutes	Medium
	Monitor alternative route operations and safety performance in real-time	Medium
	Optimize contractor work periods	Medium
Traveler Information Goals	Provide roadway users real-time work zone information	Medium
	Provide roadway users real-time alternate route information	Medium

Next, the Feasibility Wizard was used to answer a series of questions related to work zone duration, impacts, and delays, along with specific issues affecting the work zone. Based on the answers to these questions, an ITS feasibility score was generated for the project. The Feasibility Wizard will provide one of three outcomes: (1) WZITS is recommended and will provide benefits, (2) WZITS may provide benefits, and (3) WZITS may not provide benefits. For this case study, the feasibility score was 36 points, which results in a recommendation that WZITS be designed and implemented for this project.

The Application Wizard was then applied to generate a recommendation for the type of WZITS to implement. A series of questions were answered that were based on the goal categories but related to the construction project. The answers to these questions were used to recommend WZITS applications, as shown in Table 2. For the I-40 case study, the top two recommended applications were:

- Queue warning system, and
- Real-time traveler information system.

**Table 2: Application Wizard Output for the Raleigh, NC Case Study**

Recommended WZITS Applications	Score
Queue Warning	High
Real-time Traveler Information	High
Incident Management	Medium
Variable Speed Limit	Medium
Performance Measurement	Medium
Dynamic Lane Merge	Medium
Temporary Ramp Metering	Low
Construction Vehicle Entrance/ Exit Warning	Low

The Stakeholder Wizard was applied to the case study to assist the NCDOT project designer with determining the project stakeholders. This wizard asks a series of questions related to the project and the land use surrounding the work zone. Based on the answers to the questions, the wizard recommended a list of potential stakeholders for the project, as shown below in Table 3.

**Table 3: Recommended Stakeholder List for the Raleigh, NC Case Study**

Recommended Stakeholders by WZITS Tool	Score
FHWA Division Office	High
Local police	High
Motorists	Medium
Traffic Management Center	Medium
Local businesses	Medium
EMS	Medium
Commercial trucking companies	Medium
Incident management agencies	Medium
State DOT	Medium
Transit agency	Medium
Fire department	Medium
Media	Medium
City transportation agency	Low
Shopping centers	Low
Local residents	Low
Special event venue	Low
County transportation agency	Low
MPO	Low
Service patrol/ contractors	Low
Construction contractors	Low
Public officials	Low
Schools/ Universities	Low
Convention/ Visitors Bureau	Low
State police	Low

Detailed case study results are provided in Section 5.

### 3.2 CASE STUDY 2: BRIDGE REPLACEMENT IN ANDOVER, MA

In this case study, the Massachusetts Department of Transportation (MassDOT) plans to replace a bridge on Interstate 495 that crosses over Route 28 in Andover, MA. Figure shows an aerial view of the project location.



**Figure 3: Overview of the Bridge Replacement Case Study in Andover, MA**

The project will take place over a four-year staged construction project. The construction project will have the following four stages:

- Stage 1 (6 months) — Construct a temporary bridge in the existing median.
- Stage 2 (18 months) — Move I-495 northbound traffic to the temporary bridge, demolish the existing I-495 northbound bridge and reconstruct a new I-495 northbound bridge.
- Stage 3 (18 months) — Move I-495 northbound traffic to the new bridge, shift I-495 southbound traffic to the temporary bridge, demolish the I-495 southbound bridge and reconstruct a new I-495 southbound bridge.
- Stage 4 (6 months) – Shift traffic to the newly constructed I-495 southbound bridge and remove the temporary bridge in the median.

Various traffic characteristics are known about the roadway and about the temporary bridge that will be constructed. Following the guidance in *Work Zone ITS Implementation Guide* and the implementation tool's wizards, the information about the bridge replacement project was used to complete Steps 1 and Step 2 of the work zone ITS assessment process and determine the following:

- System goals,
- Feasibility of the project as a Smart Work Zone,
- Most applicable Smart Work Zone applications, and
- List of stakeholders.

Starting with the Goal Wizard, a series of twenty (20) questions were answered related to the roadway geometry, expected congestion and queuing, and performance targets. Based on the responses, the goal wizard output matrix provided a number of goals in the mobility, safety, productivity, regulatory, and traveler information categories and also provided a ranking for each of the associated goals (see Table 6).

The Goal Wizard assists agencies in determining goals for their projects. For the I-495 case study, the highest ranked goal is in the safety category: reduce rear-end crashes. Additional goals include reducing secondary crashes and incident clearance times. In the mobility category, it is recommended that delays are reduced to within MassDOT's adopted 12-minute rule and to reduce travel time variability.

**Table 4: Goal Wizard Output for the Andover, MA Case Study.**

Category	Recommended User Goals by WZITS Tool	Score
<b>Mobility Goals</b>	Reduce daily peak period delays to 12 minutes	Medium
	Reduce variability of travel times	Medium
	Facilitate the movement of emergency and construction vehicles through the work zone	Medium
	Reduce the number of single-vehicle trips through the work zone	Medium
<b>Safety Goals</b>	Reduce rear-end crashes	High
	Reduce secondary incidents	Medium
	Reduce Incident Clearance Times	Medium
	Provide a safe environment for roadway users and worker safety	Medium
	Work toward zero work zone fatalities	Medium
<b>Productivity Goals</b>	Minimize delays in construction vehicle access to the work zone	Low
	Provide an egress from work zone for haul vehicles	Low
<b>Regulatory Goals</b>	Monitor work zone operations and safety performance in real-time	Medium
	Reduce work zone delays to within XX minutes	Medium
	Monitor alternative route operations and safety performance in real-time	Low
	Optimize contractor work periods	Low
<b>Traveler Information Goals</b>	Provide roadway users real-time work zone information	Low
	Provide roadway users real-time alternate route information	Low

Next, the Feasibility Wizard was used to answer a series of questions related to the work zone duration, impacts, and delays, along with specific issues affecting the work zone. Based on the answers to these questions, an ITS feasibility score was generated for the project. The Feasibility Wizard will provide one of three outcomes: (1) WZITS is recommended and will provide benefits, (2) WZITS may provide benefits, and (3) WZITS may not provide benefits. For this case study, the feasibility score was 37 points, which results in a recommendation that WZITS be designed and implemented for this project.

The Application Wizard was then applied to generate a recommendation for the type of WZITS to implement. A series of questions were answered that were based on the goal categories but related to the construction project. The answers to these questions were used to recommend

WZITS applications, as shown in Table 5. For the I-495 case study, the top two recommended applications to be implemented are:

- Real-time traveler information system, and
- Queue warning system.

**Table 5: Application Wizard Output for the Andover, MA Case Study.**

Recommended WZITS Applications	Score
Real-time Traveler Information	High
Queue Warning	Medium
Incident Management	Low
Variable Speed Limit	Low
Performance Measurement	Low
Dynamic Lane Merge	Low
Automated Enforcement	Low
Construction Vehicle Entrance/ Exit Warning	Low
Temporary Ramp Metering	Low

The Stakeholder Wizard was applied to the case study to assist the MassDOT project designer with determining the project stakeholders. The stakeholder wizard asks the user a series of questions related to the project and the land use surrounding the work zone. Based on the answers to the questions, the wizard recommends a list of potential stakeholders for the project, as shown below in Table 6.

**Table 6: Recommended Stakeholder List for the Andover, MA Case Study.**

Recommended Stakeholders by WZITS Tool	Score
Traffic Management Center	High
Commercial trucking companies	Medium
Motorists	Medium
Local businesses	Medium
State DOT	Low
Service patrol/ contractors	Low
Construction contractors	Low
EMS	Low
Media	Low
Incident management agencies	Low
Local police	Low
County transportation agency	Low
MPO	Low
FHWA Division Office	Low
Fire department	Low
Public officials	Low
City transportation agency	Low
State police	Low
Shopping centers	Low
Local residents	Low
Special event venue	Low

Detailed case study results are provided in Section 5.



### 3.3 CASE STUDY 3: NORTH WASHINGTON BRIDGE IN BOSTON, MA

The Massachusetts Department of Transportation (MassDOT), in conjunction with the City of Boston, plans to replace the North Washington Street Bridge between Boston's North End and Charlestown neighborhoods. Figure shows the project limits. Detailed evaluation results and reports generated with the WZITS tool are shown in the Appendix.



**Figure 4: North Washington Street Bridge Project (Source: MassDOT).**

The project will take place over a three-year staged construction project. The construction project will have the following four stages (and sub-stages):

- Stage 1A — Closes the sidewalk on the east side of the bridge and establishes the work zone. Shared bicycle lane markings (sharrows) are added.
- Stage 1B — Reduces the bridge capacity from four lanes to two lanes with all travel on the west side of the bridge. Detours are put in place.
- Stage 2 — Provides an additional travel lane for a total of three lanes: one inbound into the North End and two outbound exiting the North End.
- Stage 3 — Shifts the three lanes of traffic to the east side of the bridge.
- Stage 4A — Reopens all four lanes for travel and provides a one-way buffered bicycle lane and sidewalk on the west side of the bridge.



- Stage 4B — Maintains the travel lanes provided in Stage 4A but the transition areas entering and exiting the bridge structure shift the work zones to allow the final stages of the project to tie into the existing City streets.

Various traffic characteristics are known about the roadway and the planned work zone. Using the implementation tool, the following information was completed for the project:

- Assessment of Needs;
- Concept Development and Feasibility;
- Detailed System Planning and Design;
- Procurement;
- System Deployment; and
- System Operation, Maintenance, and Evaluation.

The Goal Wizard provided recommended user goals, as shown in Table 7. The WZITS feasibility score generated by the Feasibility Wizard was 35. A score of 30 or more suggests that ITS is likely to provide significant benefits and should be considered as a treatment to mitigate impacts. Based on the project goals and the overall WZITS feasibility, the Application Wizard then provided a set of recommended work zone ITS applications, as shown in Table 8.

**Table 7: Goal Wizard Output for the Boston, MA Case Study.**

Category	Recommended User Goals by WZITS Tool	Priority
<b>Safety Goals</b>	Work toward Zero work zone fatalities	Medium
	Reduce rear-end crashes	Medium
	Provide safe environment for roadway users and worker safety	Low
<b>Mobility Goals</b>	Reduce variability of travel times	Medium
	Reduce the number of single-vehicle trips through the work zone	Medium
<b>Regulatory Goals</b>	Optimize contractor work periods	Low
<b>Traveler Info Goals</b>	Provide roadway users real-time work zone information	Medium
	Provide roadway users real-time alternative route information	Medium

**Table 8: Application Wizard Output for the Boston, MA Case Study.**

Recommended WZITS Applications	
Queue Warning	Medium
Real-time Traveler Information	High
Incident Management	Low
Dynamic Lane Merge	Low
Variable Speed Limit	Medium
Automated Enforcement	Low
Construction Vehicle Entrance/ Exit Warning	Not Recommended
Temporary Ramp Metering	Low
Performance Measurement	Medium

The WZITS tool recommended that one or more ITS solutions be incorporated into the project, along with a number of identified goals for the deployment. The tool further identified a number of potential strategies to consider for the project. Detailed case study results are provided in Section 5.

### 3.4 CASE STUDY 4: ROADWAY WIDENING IN ASHE COUNTY, NC

The North Carolina Department of Transportation (NCDOT) is widening U.S. 221 from U.S. 421 in Deep Gap to U.S. 221 Business/N.C. 88 in Jefferson, NC. The 16.1-mile project will widen the main corridor into Ashe County for commuters and commercial vehicles into a four-lane median-divided highway. **Error! Reference source not found.** provides an overview map of the project.




Figure 5: NCDOT US 221 Case Study Overview (Source: NCDOT).

As planned, the project work includes the following five sections:

- Section A — U.S. 421 to Idlewild Road in Watauga and Ashe counties (2.8 miles)
- Section B — Idlewild Road to North of South Fork New River in Ashe County (1.8 miles)
- Section C — South Fork New River to South of N.C. 194 in Ashe County (4 miles)
- Section D — South of N.C. 194 to North of N.C. 163 in Ashe County (4 miles)
- Section E — N.C. 163 to U.S. 221 Business/N.C. 88 in Jefferson (3.5 miles)

Various traffic characteristics are known about the roadway and the planned work zone. Using the implementation tool, the following information was completed for the project:

- Assessment of Needs;

- Concept Development and Feasibility;
- Detailed System Planning and Design;
- Procurement;
- System Deployment; and
- System Operation, Maintenance, and Evaluation.

Applying the Goal Wizard generated the set of recommended user goals shown in Table 9. The WZITS feasibility score generated by the Feasibility Wizard was 20. This score suggests that ITS may provide some benefits on the predominantly rural facility, and should be considered as a treatment to mitigate impacts. Based on the project goals, the Application Wizard then provided a set of recommended WZ ITS applications, which are summarized in Table 10.

**Table 9: Goal Wizard Output for the US 221 Case Study.**

Category	Recommended User Goals by WZITS Tool	Priority
<b>Safety Goals</b>	Reduce secondary incidents	Medium
	Reduce incidence clearance times	Medium
	Work towards zero work zone fatalities	Medium
	Provide a safe environment for roadway users and worker safety	Medium
<b>Productivity Goals</b>	Provide an egress from work zone for haul vehicles	Low
<b>Regulatory Goals</b>	Optimize contractor work periods	Low

**Table 10: Application Wizard Output for the US 221 Case Study.**

Recommended WZITS Applications	
Queue Warning	Low
Real-time Traveler Information	Low
Incident Management	Low
Dynamic Lane Merge	Not Recommended
Variable Speed Limit	Low
Automated Enforcement	Low
Construction Vehicle Entrance/ Exit Warning	Low
Temporary Ramp Metering	Low
Performance Measurement	Medium

The implementation tool recommended that one or more ITS solutions should be considered for the project, and identified a number of potential goals for the deployment. The tool further identified a number of potential strategies to consider for the project, although they generally scored low compared to the previous case studies. Detailed case study results are provided in Section 5.

## 4 REFERENCES

Federal Highway Administration, Work Zone Intelligent Transportation Systems Implementation Guide, January 2014

Massachusetts Department of Transportation. 2017.

North Carolina Department of Transportation. 2017.

## 5 APPENDIX - DETAILED CASE STUDY TOOL REPORTS

The following pages contain the output reports for the four case studies generated using the WZITS Implementation Tool. Each report consists of eight pages, formatted to contain the most pertinent inputs and outputs generated from the WZITS tool.